AMENDMENT NO. 1 AUGUST 2019
TO
IS 16444 (PART 2) : 2017 a.c. STATIC TRANSFORMER OPERATED WATTHOUR AND VAR-HOUR SMART METERS, CLASS 0.2S, 0.5S AND 1.0S

PART 2 SPECIFICATION TRANSFORMER OPERATED SMART METERS

(*Page* 6, *clause* **9.2**, *para* 1) — Substitute the following for the existing para:

'Type test shall be made on minimum one or more specimens (1st Set) selected by the manufacturer and test sequence shall be as given in Table 1. Each specimen shall comply with all the tests given in Table 1. In case of one test specimen failing to comply in any respect, further same number(s) of specimen(s) (equivalent to 1st set) shall be taken, all of which shall comply with requirements of standard given in Table 1.

In addition, one additional sample shall comply with data exchange protocol requirement of this standard.

For acceptance test, recommended sampling plan and the criteria for acceptance of the lot are given in relevant Annex of IS 14697.'

(ETD 13)

Publication Unit, BIS, New Delhi, India